



RLH Industries, Inc.

PRODUCT INFORMATION

The leader in
fiber optic
telecommunications
technology.

R2009B-052709

TELCO TURN-KEY UNITS

PRE-CONFIGURED CABINETS AND PEDESTALS

RLH Telco Turn-key Units are pre-configured cabinets and pedestals that offer a fast and convenient way to set up a fiber optic Link / Telco Demarc system outside the ZOI or at the CFJ. Systems include RLH Card Shelf pre-wired to a terminal, terminal test lead, 25 pair gas tube protected terminal and 8 or 14 card NIU Housing.

Turn-key units offer rapid and uniform installation at the job site and are ready for fiber and telco plug-in. Telco Turn-key units offer substantial cost savings and have all necessary copper and fiber equipment housings and connection terminals pre-installed and pre-wired.

Turn-key Telco Units can be installed into RLH Type-03/07 pedestals, galvanized steel, aluminum or fiberglass cabinets, and are covered by our lifetime warranty.

Contact us for individualized configurations available through our factory modification program.



Standard Features

- Turn-key Telco units are ready to install
- Fire treated 3/4" backboard
- Include RLH Fiber Card Shelf pre-wired to terminal
- Included test terminal and 25 pair gas tube protected terminal, pre-wired
- Pre-wired 8 or 14 card NIU housing
- Saves hours in labor setup
- Let technicians concentrate on setup and testing rather than wiring and mounting
- Rapid setup at job site
- Individualized configurations available
- Exclusive lifetime warranty



Turn-key Telco Unit Type-07, RLH Side



Turn-key Telco Unit Type-07, Customer Side



Turn-key Telco Unit, Fiberglass Cabinet

Pedestal Turn-key Telco Units

Part Number	Description	Pedestal
8806-1409-03TT	Turn-key Telco Unit with 5 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Type-03
8806-1406-03TT	Turn-key Telco Unit with 8 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Type-03
8806-1409-07TT	Turn-key Telco Unit with 5 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Type-07
8806-1406-07TT	Turn-key Telco Unit with 8 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Type-07
8806-1408-07TT	Turn-key Telco Unit with 12 card shelf, terminal, test lead, 25 pair protected terminal, 14 Card NIU Housing	Type-07

* **Note:** Add **MS** to part number to include 2 ea. 32" mounting stakes

Cabinet Turn-key Telco Units

Part Number	Description	Cabinet*
8806-0024-01G5IPT	Turn-key Telco Unit with 5 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Galvanized Steel H36xW30xD13
8806-0024-01G8IPT	Turn-key Telco Unit with 8 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Galvanized Steel H36xW30xD13
8806-0024-01G12IPT	Turn-key Telco Unit with 12 card shelf, terminal, test lead, 25 pair protected terminal, 14 Card NIU Housing	Galvanized Steel H36xW30xD13
8806-1296-01G5IPT	Turn-key Telco Unit with 5 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Galvanized Steel H40xW32xD15
8806-1296-01G8IPT	Turn-key Telco Unit with 8 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Galvanized Steel H40xW32xD15
8806-1296-01G12IPT	Turn-key Telco Unit with 12 card shelf, terminal, test lead, 25 pair protected terminal, 14 Card NIU Housing	Galvanized Steel H40xW32xD15

* **Note:** Substitute **A** for **G** in part number for Aluminum Cabinet instead of Galvanized. Example: 8806-0024-01**A**5IPT for Aluminum Cabinet

Part Number	Description	Cabinet
8806-1284-015IPT	Turn-key Telco Unit with 5 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Fiberglass H30xW24xD13
8806-1284-018IPT	Turn-key Telco Unit with 8 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Fiberglass H30xW24xD13
8806-1286-015IPT	Turn-key Telco Unit with 5 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Fiberglass H40xW32xD13
8806-1286-018IPT	Turn-key Telco Unit with 8 card shelf, terminal, test lead, 25 pair protected terminal, 8 Card NIU Housing	Fiberglass H40xW32xD13
8806-1286-0112IPT	Turn-key Telco Unit with 12 card shelf, terminal, test lead, 25 pair protected terminal, 14 Card NIU Housing	Fiberglass H40xW32xD13



RLH Industries, Inc.
 936 N. Main Street, Orange, CA 92867 USA
 T: (714) 532-1672
 F: (714) 532-1885

Please contact your RLH sales representative for pricing and delivery information.

Specifications subject to change without notice. TTU-05-09